

BID FORM**BRIDGE REPLACEMENT PROJECT****ERBR-36(01)****FUDGETOWN ROAD (C.R. NO. 418)****FOR THE BOARD OF SUPERVISORS LAFAYETTE COUNTY, MISSISSIPPI****August 14, 2025****9:00 a.m.****I, WE AGREE TO COMPLETE THIS PROJECT WITHIN 120 WORKING DAYS.**

BID		APPROX		UNIT PRICE		AMOUNT	
ITEM NO.	DESCRIPTION	QUANTITY	UNIT	DOLLARS	CENTS	DOLLARS	CENTS
	<u>ROADWAY ITEMS</u>						
S-200-A	Mobilization	1	LS	XXXXX	XXXXX		
S-201-A	Clearing and Grubbing	1	LS	XXXXX	XXXXX		
S-202-B	Removal of Bridge (STA. 34+31)	1	UNIT				
S-202-E	Removal of Pipe (All sizes)	40.0	LF				
901-S-202-F	Remove and Relay Riprap	100.0	SY				
S-203-A	Unclassified Excavation (F.M.)	610.0	CY				
S-203-E1	Borrow Excavation (F.M.E.) (Contractor Furnished)(Class 9)	1,089.0	CY				
S-304-B	Granular Material (Class 4, Group "C")	670.0	TON				
S-304-D	Crushed Stone (Size 610)	198.0	TON				
S-310-D	Mixing, Shaping and Compaction	78.0	CY				
S-403-A	Hot Mix Asphalt, ST, 9.5 mm	157.0	TON				
S-403-A	Hot Mix Asphalt, ST, 12.5 mm	189.0	TON				
S-403-A	Hot Mix Asphalt, ST, 19 mm	382.0	TON				
S-406-A	Cold Milling of Bituminous Pavement, All Depths	667.0	SY				
901-S-423-A	Rumble Strips, Ground-In	0.261	MILE				
S-603-PE	24" Corrugated Polyethylene Pipe	80.0	LF				
S-606-B	Guard Rail, W-Beam	26.0	LF				

BID		APPROX		UNIT PRICE		AMOUNT	
ITEM NO.	DESCRIPTION	QUANTITY	UNIT	DOLLARS	CENTS	DOLLARS	CENTS
S-606-D	Guard Rail, Bridge End Section, Type "I", Thrie Beam	4	EACH				
S-606-E	Guard Rail, Terminal End Section	4	EACH				
S-617-A	Right-of-Way Markers (Type I)	9	EACH				
S-618-A	Maintenance of Traffic	1	LS	xxxxx	xxxxx		
S-618-B	Additional Construction Signs	0	SF	10	00	\$	00 00
S-621-C	4" Wide Thermoplastic Edge Stripe (Continuous White) (60 MIL)	0.314	MILE				
S-621-E1	4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 MIL)	1,660.0	LF				
S-627-L	Two-way Yellow High Performance Raised Markers	22	EACH				
S-630-C	Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4	EACH				
S-630-D	Reflectorized Traffic Delineator Sign (Encapsulated Lens)	17	EACH				
S-630-G	Reflectorized Traffic Warning Sign with Supp. Plate (Encapsulated Lens)	2	EACH				
SUBTOTAL ROADWAY ITEMS:							
	<u>EROSION CONTROL ITEMS</u>						
S-212-B	Commercial Fertilizer (13:13:13)	0.95	TON				
S-212-F	Ammonium Nitrate	0.10	TON				
S-214-A	Seeding	0.95	ACRE				
S-215-A	Vegetative Materials for Mulch	2.85	TON				
S-227-A	Excelsior Blanket	500.0	SY				
S-233-A	Temporary Silt Fence (Type I)(AOS 0.15 mm - 0.84 mm)	1,600.0	LF				
237-A	Wattles, 20"	80.0	LF				

BID		APPROX		UNIT PRICE		AMOUNT	
ITEM NO.	DESCRIPTION	QUANTITY	UNIT	DOLLARS	CENTS	DOLLARS	CENTS
S-815-A	Loose Riprap (300 LB)	80.0	TON				
S-815-E	Geotextile Under Riprap (Type V) (AOS 0.21 mm - 0.43 mm)	240.0	SY				
SUBTOTAL EROSION CONTROL ITEMS:							
	<u>BRIDGE ITEMS</u>						
S-803-A	Test Pile	2	EACH				
S-803-B	Conventional Static Pile Load Test	0	EACH				
S-803-C	18" Prestressed Concrete Piling	1,710.0	LF				
S-803-F	22" Pre-formed Pile Hole	190.0	LF				
901-S-804-A	Bridge Concrete, Class "A"	186.56	CY				
901-S-804-C	40' Prestressed Concrete Beam, Type I + 2	307.50	LF				
901-S-804-C	80' Prestressed Concrete Beam, Type III	398.75	LF				
S-805-A	Reinforcement	32,245	LB				
S-813-A	Concrete Railing	284.0	LF				
S-815-A	Loose Riprap, 300 LB	493.0	TON				
S-815-E	Geotextile Under Riprap (Type V) (AOS 0.21 mm - 0.43 mm)	950.0	SY				
SUBTOTAL BRIDGE ITEMS:							
TOTAL BID:							