

BIDS RECEIVED:

Town of Byhalia
NATURAL GAS SERVICES FOR
175 AND 177 WINGO ROAD EXTENDED
CHICKASAW TRAILS INDUSTRIAL PARK
BYHALIA, MISSISSIPPI


BID ITEM NO.	DESCRIPTION	APPROX QUANTITY	UNIT	ENGINEERING ESTIMATE		Brocato Construction, Inc. Batesville, MS 38606 MS Certification: 09590-MC		Eubank Construction Co. Booneville, MS 38829 MS Certification: 10589-MC		Revell Construction Company, In Union City, TN 38281 MS Certification: 13148	
				UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
BASE BID ITEMS											
1	2" IPS PE 2406 SDR 11 GAS SERVICE, BORE, MINIMUM DEPTH OF COVER AS PER PLAN SHEET	256	L.F.	\$ 35.00	\$ 8,960.00	\$ 21.00	\$ 5,376.00	\$ 50.00	\$ 12,800.00	\$ 52.80	\$ 13,516.80
2	2" IPS PE 2406 SDR 11 GAS SERVICE, OPEN TRENCH	745	L.F.	\$ 11.20	\$ 8,344.00	\$ 15.75	\$ 11,733.75	\$ 12.00	\$ 8,940.00	\$ 26.90	\$ 20,040.50
3	2" IPS PE2406 BALL VALVE, FULL PORT, QUARTER TURN ON-OFF, AS PER ASTM D-2513, SDR11, BUTT FUSION ENDS, NORDSTROM #84111, WITH C.I.	3	EACH	\$ 600.00	\$ 1,800.00	\$ 288.80	\$ 866.40	\$ 650.00	\$ 1,950.00	\$ 819.00	\$ 2,457.00
4	2" X 6" IPS PE MED. DENSITY SADDLE FUSION TAPPING TEE, HIGH VOLUME	1	EACH	\$ 500.00	\$ 500.00	\$ 262.50	\$ 262.50	\$ 600.00	\$ 600.00	\$ 756.00	\$ 756.00
5	2" X 2" X 2" IPS PE 2406 SDR 11 TEE, BUTT FUSION	2	EACH	\$ 120.00	\$ 240.00	\$ 36.75	\$ 73.50	\$ 350.00	\$ 700.00	\$ 137.00	\$ 274.00
6	2" IPS ELECTROFUSION COUPLING FOR PE2406 SDR11 PIPE	2	EACH	\$ 100.00	\$ 200.00	\$ 36.75	\$ 73.50	\$ 400.00	\$ 800.00	\$ 165.00	\$ 330.00
7	2" IPS PE 2406 SDR 11 END CAP, BUTT FUSION	1	EACH	\$ 75.00	\$ 75.00	\$ 36.75	\$ 36.75	\$ 180.00	\$ 180.00	\$ 107.00	\$ 107.00
8	PREFABRICATED COMMERCIAL METER CENTER, 15C DRESSER ROTARY METER WITH EMCORRECTOR, VALVES, REGULATOR WITH 5 PSI SET POINT AND RELIEF VALVE, FITTINGS, FILTER, TESTING NOZZLES, FLANGES, BOLTS, NUTS, GASKETS AND ASSOCIATED S.S. TUBING AND S.S. FITTINGS, SOLAR COLLECTOR CHARGING SYSTEM AND MODEM FOR REMOTE METER READING, GAS FLOW LEFT TO RIGHT, 5 PSIG DELIVERY PRESSURE, TOWN OF BYHALIA WILL PROVIDE METER BID ITEM MATERIALS, THEREFORE THIS BID ITEM IS INSTALLATION COST ONLY	2	EACH	\$ 1,500.00	\$ 3,000.00	\$ 1,155.00	\$ 2,310.00	\$ 1,800.00	\$ 3,600.00	\$ 3,420.00	\$ 6,840.00
9	PREBENT ANODELESS RISER WITH FLANGED END, 2" NOM. O.D. CARBON STEEL X 2" IPS PE 2406 SDR 11, DIMENSIONS 36" VERTICAL X 34" HORIZONTAL, STEEL GRADE A53/API 5L GRADE B MIN. STRENGTH, PE BUTT FUSION END X 2" NOM. O.D. ANSI 150 FLANGED END, 5/8 X 3 1/4" ALL THREAD STUD BOLTS GR. B7 ALLOY WITH 2 GRADE 2H HEX NUTS AS PER ASTM A193 AND A194. ELSTER PERFECTION OR EQUAL.	2	EACH	\$ 1,200.00	\$ 2,400.00	\$ 735.00	\$ 1,470.00	\$ 600.00	\$ 1,200.00	\$ 964.00	\$ 1,928.00

BIDS RECEIVED:

Town of Byhalia
NATURAL GAS SERVICES FOR
175 AND 177 WINGO ROAD EXTENDED
CHICKASAW TRAILS INDUSTRIAL PARK
BYHALIA, MISSISSIPPI

BID ITEM NO.	DESCRIPTION	APPROX QUANTITY	UNIT	ENGINEERING ESTIMATE		Brocato Construction, Inc. Batesville, MS 38606 MS Certification: 09590-MC		Eubank Construction Co. Booneville, MS 38829 MS Certification: 10589-MC		Revell Construction Company, Inc. Union City, TN 38281 MS Certification: 13148	
				UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
10	415 SENSUS METER CENTER AND REGULATOR WITH 0.25 PSI SET POINT, ANODELESS RISER, VALVE AND FITTINGS, TOWN OF BYHALIA WILL PROVIDE METER BID ITEM MATERIALS, THEREFORE THIS BID ITEM IS INSTALLATION COST ONLY	1	EACH	\$ 300.96	\$ 300.96	\$ 420.00	\$ 420.00	\$ 1,800.00	\$ 1,800.00	\$ 519.00	\$ 519.00
11	3/4" IPS PE 2406 INLET PIPING X 1" NOM O.D. STEEL PIPE RISER OUTLET, ANODELESS SERVICE RISER WITH 1 GAS METER BALL VALVE, 200 PSIG, MUELLER CENTURION II MUELLER #B-31175, DUCTILE IRON BODY, DUAL O RING SEALED STEM, INTEGRAL LOCKING CAP, PTFE SEATS, OR APPROVED EQUAL.	1	EACH	\$ 179.00	\$ 179.00	\$ 472.50	\$ 472.50	\$ 800.00	\$ 800.00	\$ 458.00	\$ 458.00
12	3/4" X 2" IPS ELECTROFUSION SADDLE BASE TAPPING TEE, PE 2406, HIGH VOLUME	2	EACH	\$ 500.00	\$ 1,000.00	\$ 367.50	\$ 735.00	\$ 400.00	\$ 800.00	\$ 516.00	\$ 1,032.00
13	3/4" IPS PE 2406 PIPE, W.T. 0.095 INCHES SDR 11, SERVICE PIPE, OPEN TRENCH AND OR BORE, 30" MIN. DEPTH OF COVER	124	L.F.	\$ 6.21	\$ 770.04	\$ 21.00	\$ 2,604.00	\$ 35.00	\$ 4,340.00	\$ 37.00	\$ 4,588.00
14	TRACER WIRE PE30-12 GA., POLYETHYLENE JACKETED 30 MILS THICK, 12 GA. COPPER WIRE, LABELED FOR NATURAL GAS WITH 3M - PART # DBY/DBR DIRECT BURY SPLICE KIT	1,125	L.F.	\$ 0.25	\$ 281.25	\$ 0.26	\$ 295.87	\$ 0.20	\$ 225.00	\$ 1.25	\$ 1,406.25
15	3/4" IPS PE2406 BALL VALVE, FULL PORT, QUARTER TURN ON-OFF, AS PER ASTM D-2513, SDR11, BUTT FUSION ENDS, NORDSTROM, WITH C.I. VALVE BOX ASSEMBLY	2	EACH	\$ 500.00	\$ 1,000.00	\$ 472.50	\$ 945.00	\$ 600.00	\$ 1,200.00	\$ 632.00	\$ 1,264.00
16	6" NOM. O.D. x 5' 6" PROTECTIVE POSTS/CONCRETE FOOTINGS	8	EACH	\$ 500.00	\$ 4,000.00	\$ 630.00	\$ 5,040.00	\$ 500.00	\$ 4,000.00	\$ 1,480.00	\$ 11,840.00
17	SILT FENCE, STAKES AND BACKING	100	L.F.	\$ 1.50	\$ 150.00	\$ 8.40	\$ 840.00	\$ 2.00	\$ 200.00	\$ 4.15	\$ 415.00
18	STRAW HAY FOR EROSION CONTROL	16	BALES	\$ 10.00	\$ 160.00	\$ 26.25	\$ 420.00	\$ 5.00	\$ 80.00	\$ 8.30	\$ 132.80
19	MOBILIZATION	1	L.S.	\$ 3,000.00	\$ 3,000.00	\$ 2,625.00	\$ 2,625.00	\$ 5,500.00	\$ 5,500.00	\$ 9,845.00	\$ 9,845.00
TOTAL BID:				\$	36,360.25	\$	36,599.77	\$	49,715.00	\$	77,749.35

I CERTIFY THIS TO BE A TRUE AND ACCURATE TABULATION OF ALL BIDS RECEIVED:


 Larry L. Britt, PE/PS
 Consulting Engineer

5/19/20
 DATE