

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Marshall County, Mississippi at the Marshall County Courthouse, 107 Market St., Holly Springs, MS 38635 until 10:00 a.m. local time on the 11th day of January, 2023 and shortly thereafter publicly opened and read aloud for the construction of 0.334 miles of BRIDGE REPLACEMENT PROJECT on BETHLEHEM ROAD being known as Project No. CRSA-0977-00(002) 107029-701000) in Marshall County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

<u>ITEM</u>	<u>QUANTITY</u>	<u>UNIT</u>
<u>ROADWAY BASE BID ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE (STA. 431+97)	1.000	UN
REMOVAL OF ASPHALT (ALL DEPTHS)	1,446.000	SY
UNCLASSIFIED EXCAVATION (F.M.)	1,069.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	4,161.000	CY
GEOTEXTILE STABILIZATION, TYPE V, NON-WOVEN	1,661.000	SY
GRANULAR MATERIAL (LVM), (CLASS 4, GROUP "C") CRUSHED STONE	203.000	TON
	702.000	TON
HOT MIX ASPHALT, (ST) (9.5 mm)	134.000	TON
HOT MIX ASPHALT, (ST) (12.5 mm)	134.000	TON
CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	3.100	CY
REINFORCING STEEL	148.000	LB
36" REINFORCED CONCRETE PIPE, CLASS III	32.000	LF
36" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
GUARD RAIL, W-BEAM	50.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE "I", THRIE BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MIL)	0.650	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MIL)	3,530.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 MIL)	42.000	LF
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	2.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	1.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA
<u>EROSION CONTROL BASE BID ITEMS:</u>		
COMMERCIAL FERTILIZER (13:13:13)	2.000	TON
AMMONIUM NITRATE	0.200	TON
SEEDING	2.000	AC
VEGETATIVE MATERIALS FOR MULCH	4.000	TON
TEMPORARY SILT FENCE (TYPE I) (AOS 0.15 mm - 0.84 mm)	1,500.000	LF
WATTLES, 20"	200.000	LF
LOOSE RIPRAP, 300 LB	150.000	TON

GEOTEXTILE UNDER RIPRAP, (TYPE V), (AOS NON-WOVEN < 0.43 mm)	240.000	SY
 <u>BRIDGE ITEMS:</u>		
TEST PILE	7.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
18" PRESTRESSED CONCRETE PILING	8,130.000	LF
22" PRE-FORMED PILE HOLE	820.000	LF
BRIDGE CONCRETE, CLASS "A"	597.790	CY
31' PRESTRESSED CONCRETE BEAM, TYPE I & 2	153.750	LF
40' PRESTRESSED CONCRETE BEAM TYPE I & 2	397.500	LF
100' PRESTRESSED CONCRETE BEAM, TYPE IV	997.500	LF
REINFORCEMENT	112,669.000	LB
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	24.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	102.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	8.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	34.000	EA
PRECAST CONCRETE BARRIER RAIL	1,608.000	LF
CONCRETE RAILING	622.000	LF
LOOSE RIPRAP, 300 LB	252.000	TON
GEOTEXTILE UNDER RIPRAP (TYPE V) (AOS NON-WOVEN < 0.43 mm)	450.000	SY

NOTICE TO CONTRACTORS: CRSA-0977-00(002) 107029-701000)
CONTRACT TIME: 300 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement; minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Marshall County, and the County Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Larry L. Britt, County Engineer for Marshall County, Mississippi, P.O. Box 308, 823 North Lamar Blvd., Oxford, MS 38655, 662-234-1763. The Cost is seventy-five dollars (\$75.00) for plans and thirty dollars (\$30.00) for the proposal, non-refundable certified check or bid bond for five percent (5%) of the total bid, made payable to Marshall County and the State of Mississippi must accompany each proposal.

Bid preparation will be in accordance with Section 00200 - Instructions to Bidders bound in the Project Manual. Project Plans and Project Manual may be examined at www.centralbidding.com.

Official bid documents can be downloaded at www.centralbidding.com. Electronic bids may be submitted at www.centralbidding.com. For any questions relating to

